

This Listing of Claims will replace all prior versions, and listings, of claims in the application:

### **LISTING OF CLAIMS**

1. (Currently Amended) A method of desalinating water in a plurality of stages comprising membrane module units, wherein permeate water from a first stage membrane module unit is supplied to a second stage membrane module unit to obtain desalinated water therefrom, the method comprising:

processing at least a portion of a feed water having a total salt concentration of 3.0 to 4.8% by weight and a calcium ion concentration of 200 to 500 mg/l, wherein said at least a portion of the feed water is treated with the first stage membrane module unit ~~to obtain the permeate water, said permeate water being optionally mixed with an additional portion of the feed water~~ to produce a second stage intake water, the second stage intake water having a total salt concentration of about 55 to 90% of that of the feed water and a calcium ion concentration of about 95% or less of that of the feed water; and

supplying the second stage intake water to the second stage membrane module unit, thereby obtaining the desalinated water.

2. (Original) A method according to Claim 1, wherein the feed water has a sulphate ion concentration of 1500 to 3500 mg/l and the sulphate concentration is adjusted to 80% or less of that of the feed water by the first step.

3. (Original) A method according to Claim 1, wherein 30 to 100% of the amount of the feed water is treated with the first stage membrane module unit, and then mixed with untreated feed water and supplied to the second stage membrane module unit.

4. (Original) A method according to Claim 3, wherein 35 to 95% of the amount of the feed water is treated with the first stage membrane module unit, and then mixed with untreated feed water and supplied to the second stage membrane module unit.

5. (Original) A method according to Claim 4, wherein 40 to 90% of the amount of the feed water is treated with the first stage membrane module unit, and then mixed with untreated feed water and supplied to the second stage membrane module unit.

6. (Original) A method according to Claim 1, carried out such as to provide, from the water supplied to the first stage membrane module unit, permeate water and concentrate water, the amount of permeate water, expressed as a percentage of the total amount of water supplied, being within the range of 65% to 95%.

7. (Original) A method according to Claim 6, wherein the said percentage amount of permeate water is within the range of 75% to 90%.

8. (Original) A method according to Claim 1, carried out such as to provide, from the water supplied to the second stage membrane module unit, permeate water and concentrate water, the percentage amount of permeate water, expressed as a percentage of the total amount of water supplied, being within the range of 70% to 85%.

9. (Original) A method according to Claim 1, carried out such that the total amount of permeate water from the second stage membrane module unit, expressed as a percentage of the amount of feed water (so-called total recovery ratio), is within the range of 60% to 80%.

10. (Original) A method according to Claim 9, wherein the said percentage amount of permeate water from the second stage membrane module unit is within the range of 65% to 75%.

11. (Original) A method according to Claim 1, wherein a nanofiltration membrane unit is used for the first stage membrane module unit and a reverse osmosis membrane unit is used for the second stage membrane module unit.

12. (Original) A method according to Claim 11, wherein the first stage nanofiltration membrane module unit has at least first and second membrane components at respective first and second sub-stages of the first stage, each said membrane component providing permeate water and concentrate water and wherein concentrate water from a first sub-stage nanofiltration membrane module component is supplied to a second sub-stage nanofiltration membrane module component.

13. (Original) A method according to Claim 11, wherein the second stage reverse osmosis membrane module unit has at least first and second membrane components at respective first and second sub-stages of the second stage, each said membrane component providing permeate water and concentrate water and wherein concentrate water from a first sub-stage reverse osmosis membrane module component is supplied to a second sub-stage reverse osmosis membrane module component.

14. (Original) A method according to Claim 13, wherein the pressure of concentrate water from the first sub-stage reverse osmosis membrane module component is boosted and the concentrate water then supplied to the second sub-stage reverse osmosis membrane module component to obtain desalinated water.

15. (Currently Amended) A method according to Claim 14, wherein, in a plurality of sub-stages at which reverse osmosis membrane module components are disposed, the relation between the operating pressure  $P(n)$  of the first sub-stage reverse osmosis membrane module component and the operating pressure  $P(n + 1)$  of the second sub-stage reverse osmosis membrane module component is in a range given by the expression

$$1.15 \leq P(n + 1) / P(n) \leq 1.8.$$

16. (Original) A method according to any one of Claims 11, wherein a scale prevention agent is injected into the water supplied to the nanofiltration membrane module unit before performing nanofiltration.

17. (Original) A method according to Claim 1, wherein the feed water is filtered water processed with a microfiltration membrane or an ultrafiltration membrane.

18. (Withdrawn)

19. (Withdrawn)

20. (Withdrawn)

21. (Withdrawn)

22. (Withdrawn)

23. (Withdrawn)

24. (Withdrawn)

25. (Withdrawn)

26. (Withdrawn)

27. (New) The method of claim 1, wherein the total salt concentration of the second stage intake water is within a limit such that substantially no scales form on a membrane of the second stage membrane module after supplying the second stage intake water to the second stage membrane module unit for 24 hours.

28. (New) A method of desalinating water in a plurality of stages comprising membrane module units, wherein permeate water from a first stage membrane module unit is supplied to a second stage membrane module unit to obtain desalinated water therefrom, the method comprising processing at least a portion of a feed water having a total salt concentration of 3.0 to 4.8% by weight and a calcium ion concentration of 200 to 500 mg/l, wherein said at least a portion of the feed water is treated with the first stage membrane module unit to obtain the permeate water, said permeate water being optionally mixed with an additional portion of the feed water to produce a second stage intake water, the second stage intake water having a total salt concentration within a limit such that substantially no scales form on a membrane of the second stage membrane module after supplying the second stage intake water to the second stage membrane module, and supplying the second stage intake water to the second stage membrane module unit, thereby obtaining the desalinated water.